

Morell Engineering, Inc.
711 East Hobbs St.
Athens, AL 35611
256-867-4957
APRIL 3, 2023

ADDENDUM NO. 2

PROJECT NO.: 23-0047
OWNER: Limestone County Water and Sewer Authority
PROJECT: Elkmont Regional Pump Station and Gravity Sewer

BID DATE: April 12, 2023
TO: ALL PROSPECTIVE CONTRACTORS

The changes, modifications, and/or additions covered by and set forth in this Addendum No. 2 shall become part of and be incorporated in the Contract Documents for the above referenced project:

PERSPECTIVE BIDDER RFI:

1. What size structure is the meter pit?
4' x 4'. The structure will need to be approved by the shop drawing submittal prior to construction.
2. Can an 8' x 7' precast rectangular structure be used in lieu of a 96" diameter wet well?
Yes, an 8' x 7' precast rectangular structure is acceptable with an anti-buoyancy ring. The structure will need to be approved by the shop drawing submittal prior to construction.
3. Are exterior drops required?
An exterior drop must be used on all gravity and forcemain that is 2 feet or higher above the effluent pipe.

This Addendum No. 1 shall be attached to the front of your set of specifications and made a part of the Contract Documents. Receipt of this Addendum No. 1 shall be acknowledged on Page 3 of the Proposal Form.

Morell Engineering, Inc.

By 
Ben Duncan, P.E.

THIS IS THE LAST PAGE

Attachments to Addendum No. 2 preceding this page:

A total of 2 pages (including this page) have been included in Addendum No. 2.

All Prospective Bidders and Suppliers are requested to return this page as an acknowledgment that you have received this Addendum by e-mail. This will NOT be mailed. A copy of this Addendum may be picked up at the office of the Engineer.

Received By _____

Contractor _____

Date _____